

ZESTAWIENIE STALI KONSTRUKCYJNEJ

Symbol Nazwa	Przekrój	Długość	Pole przekroju	Masa 1 mb	Ilość	Masa 1 elementu	Masa ogólna
		[mm]	[cm ²]	[kg]	[sztuk]	[kg]	[kg]
SŁUPY RAM STALOWYCH							
S-1...3	RK 180x100x10	2610	50,90	39,96	6	104,3	625,7
S-4	RK 180x100x10	2586	59,90	47,02	2	121,6	243,2
S-5	RK 180x100x5	2610	26,70	20,96	2	54,7	109,4
S-6	RK 100x100x5	2460	18,70	14,68	2	36,1	72,2
RYGLE RAM STALOWYCH							
R-1...3	RK 180x100x10	2500	50,90	39,96	6	99,891	599,348
R-4	RK 180x100x10	3180	59,90	47,02	2	149,528	299,057
R-5	RK 180x100x5	2500	26,70	20,96	2	52,399	104,798
ELEMENTY DODATKOWE							
RK-1	RK 60x60x5	2330	10,70	8,40	12	19,571	234,850
RK-2	RK 60x60x5	2090	10,70	8,40	2	17,555	35,110
RK-3	RK 40x40x5	110	6,73	5,28	26	0,581	15,110
RK-4	RK 40x40x5	156	6,73	5,28	2	0,824	1,648
POZ.1	24x300	400	72,00	56,52	6	22,6	135,6
POZ.2	6x140	160	8,40	6,59	16	1,1	16,9
POZ.3	6x70	200	4,20	3,30	16	0,7	10,6
POZ.4	24x400	696	96,00	75,36	2	52,5	104,9
POZ.5	24x443	475	106,32	83,46	2	39,6	79,3
POZ.6	20x200	200	40,00	31,40	2	6,3	12,6
						Ciężar słupów:	1050,5
						Ciężar rygli:	1003,2
						Ciężar elementów dodatkowych:	646,5

CAŁOŚĆ:	2700,29
DODATEK NA SPOINY 1,8%:	48,61
OGÓŁEM:	2748,90